Schedule.

Sl. No.	Description of work	Unit	Quantity
1	Earthwork excavation and forming bank	1,000 C.ft.	72,000
2	Removing spoil earth	Do	30,000
3	Forming surface in platform with earth	Do	36,600
4	Forming surface in platform with gravel	Do	9,400
5	Sand ballast	Do	8,000

6		Unit	Ash pit, 50 ft. long	Rail Girder Bridge extension	Platform retaining wall
	(1) Earthwork excavation	C. ft. 1,000	4,450	280	2,000
	(2) Concrete in sand mortar	C. ft. 100	435	160	470
	(3) Burnt stone in mortar	Do	770	340	1,410
	(4) Pointing with cement	Sqr.	2·70	1·2	10
	(5) Burnt stone slabs 6" thick dressed and fixed.	S. ft.	....	16	710
	(6) Burnt stone slab dressed flooring 4" thick over 3" concrete bed.	S. ft.	140	....	....
	(7) Cement concrete slabs including fixing of rag bolts (120).	C. ft.	168	....	....
	(8) 9" dia. stoneware pipes including laying and fixing charges.	R. ft.	25	....	....

Y. K. RAMACHANDRA RAU,
Executive Engineer.

KADUR DIVISION.

Notice dated 29th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 20th September 1929, till 3 P.M., for Restoring Angadi Doddakere Major Tank, Mudgere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and seventy-five only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Angadi Doddakere, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after the acceptance of tenders.

11. Rates should be quoted for each item of work and lumpsum rates are subject to modification as per date worked out during execution.

Approximate quantities for Restoring Angadi Doddakere No. 285, Mudgere Taluk.

Particulars of work	Per	Quantity	Rate	
			In figures	In words
1. *Bund R. L.* 77·00				
Earthwork to bund including watering and tamping	C.yd.	21,906		
Providing grade stones, new	No.	20		
Do Index	..	20		
Do B. M., stones	...	2		
Do Date and Register number stone ...	..	1		
Total ...	...	...		
2. *Masonry weir R. L.* 72·50·45 long.				
Earthwork excavation chargeable to bund ...	...	...		
Surki concrete for foundation body wall and returns	C.ft.	522		
Burnt brick in surki mortar	„	1,597		
Burnt stone slabs 6" thick	S.ft.	185		
Plastering with surki mortar	S qr.	12·38		
Constructing rough stone apron with jelly backing and wedging including 3 miles lead.	C.yd.	45		
Cutting joggles in joints of slabs over body wall ...	No.	5		
Earthwork at flanks, consolidation and etc. ...	Lump	sum		
Total ...	...	...		
3. *Sluice* 67·50.				
Earthwork cutting the bund and forming for the construction of sluice chargeable to bund.	...	...		
Filling the foundation with surki concrete with stone jelly.	C.ft.	129		
Burnt brick in surki mortar	„	338		
Burnt stone slabs 6" thick	S.ft.	37		
Drilling holes in arifice slabs	No.	3		
Plastering with surki mortar	Sqr.	2		
6" cast iron pipe including carting railway frieght and fixing, etc., complete.	R.ft.	27		
Providing and fixing plug and rod with lifting arrangements, etc., complete.	Lump	sum		
Rough stone apron and wings at rear ..	Lump	sum		
Total for sluice ...	...	...		

L. A. H. WINCKLER,
Executive Engineer.

MYSORE RAILWAYS, MYSORE.

Abstract Notification dated 23rd August 1929.

Attention of the intending contractors is hereby invited to the Notice, calling for tenders for "Improvements to Railway Audit Office at Mysore", published in page 886 of Part VI of the *Mysore Gazette*, dated 22nd August 1929. Tenders will be received any day up to 2 P.M. of 2nd Septepber 1929.

Y. K. RAMACHANDRA RAU,
Executive Engineer.